


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-19246-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 10 Twp. 12 Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SE NE
Lease Owner Vye-Mallonee
Lease Name Hall "B" Well No. 1
Office Address 820 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-6 19 58
Application for plugging filed 2-6 19 58
Application for plugging approved 2-6 19 58
Plugging commenced 2-6 19 58
Plugging completed 2-6 19 58
Reason for abandonment of well or producing formation non-productive

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	225	8-5/8	225	none - cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 600', plug at 600', 1/2 sack hulls, 20 sacks cement. Plug at 210', 1/2 sack hulls, 10 sacks cement to surface.

2-25-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.
Address 820 Union Center, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. E. Mallonee (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mallonee
820 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 19 58

My commission expires December 14, 1961

Martha Gorges
Martha Gorges
Notary Public.



15-051-19246-00-00

DRILLERS' LOG

#1 Hall "D"

NE SE NE Section 10-12-17W

Ellis County, Kansas

OWNER: Vye-Mallonee
CONTRACTOR: Mallonee Drilling Company, Inc.

COMMENCED: 1-24-58
COMPLETED: 2-6-58

FROM	TO	DESCRIPTION
0	50	Surface soil and rock
50	85	Shale
85	95	Sand
95	500	Shale
500	985	Sand and shale
985	1325	Rod Ded
1325	1370	Anhydrite
1370	1715	Shale and shells
1715	1885	Shale and salt
1885	1980	Shale and lime
1980	2075	Lime
2075	2300	Shale and lime
2300	2370	Lime
2370	2700	Lime and shale
2700	2795	Shale and shells
2795	3100	Shale and lime
3100	3690	Lime
		Rotary Total Depth

CASING RECORD

8-5/8 casing set at 225' with 140 sacks common cement, 1 CC. Cement circulated.

Drill Stem Test #1, 3410 - 3445
Open 1 hour, recovered 90' oil and gas cut mud, 60' oil and gas cut watery mud, 60' muddy water. BHP 613#

Drill Stem Test #2, 3619 - 3630
Open 1 hour, recovered 10' oil cut watery mud, 50' watery mud. BHP 690#

Drill Stem Test #3, 3626 - 3648
Open 2 hours, recovered 155' muddy water. BHP 704#

Elevation 2127 RB

RECEIVED
STATE CORPORATION COMMISSION
2-25-1958
FEB 25 1958
CONSERVATION DIVISION
Wichita, Kansas

Anhydrite	1325	802
Hobbs	3313	1186
Toronto	3335	1208
Lansing K.C.	3361	1234
Arbuckle	3618	1491
Rotary Total Depth	3690	1563

Geologist: Robert D. Gensch

I hereby certify that to the best of my knowledge and belief, the above represents a true and accurate Drillers' Log of the captioned well.

R. E. Mallonee
R. E. Mallonee

State of Kansas
County of Sedgewick

Subscribed and sworn to before me this 13th day of February, 1958.

My commission expires:
December 14, 1961

PLUGGING
FILE # SEC 10 T 12 R 17 W
BOOK PAGE 83 LINE 27

Martha Gorgas
Notary Public (Martha Gorgas)