


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-051-00157-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County, Sec. 10 Twp. 12 Rge. 17 (W)
Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner Victor Drilling, Inc.
Lease Name Herman Well No. 1
Office Address 312 Court Bldg., Evansville, Ind.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 8/16/53 19
Application for plugging filed 8/16/53 19
Application for plugging approved 8/16/53 19
Plugging commenced 8/16/53 19
Plugging completed 8/16/53 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3720 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	192'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 180'. Pushed plug and 1/2 sack hulls to 180' with drill pipe. Mixed 15 sacks cement and filled hole from 180' to 105'. Filled hole to 40' mixed 10 sacks cement and filled hole from 40' to 0' with cement. Surface casing cut off 18" below ground.

9-14-1953

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Victor Drilling
Address 312 Court Bldg., Evansville, Ind.

STATE OF Indiana, COUNTY OF Vanderburgh, ss.
W. W. Keahey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Keahey
312 Court Bldg., Evansville, Ind.
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of Sept., 19 53

My commission expires 9/24/56

Georgia Fischer
Notary Public.

PLUGGING
FILE SEC 10 T 12 R 17 W
BOOK PAGE 122 LINE 36

15-051-00157-00-00

Driller's Log

NAME: Herman No. 1

LOCATION: SW SE SE, Section 10-12-17W, Ellis County, Kansas.

Date Drilling Commenced: August 7, 1953

Date Drilling Completed: August 16, 1953

Casing record: Ran 192' of 8 5/8" Surface casing. Surface set at 192' - circulated w/ 100 sacks of cement. Plug set @ 180' with 15 sacks cement. Plug set @ 40' with 10 sacks cement. Plugged 8/16/53.

FROM	TO	FORMATION
0	192	Sahle
192	415	Shale
415	710	Shale and Red Bed
710	770	Hard Sand
770	850	Shale and Red Bed
850	1000	Sand
1000	1115	Shale and shells
1115	1355	Shale and sand
1355	1395	Anhydrite
1395	1720	Shale
1720	1830	Shale and salt
1830	1955	Shale
1955	2310	Shale and lime
2310	2495	Lime
2495	2850	Shale and lime
2850	3015	Shale
3015	3247	Shale and lime
3247	3390	Lime and shale
3390	3399	Shale
3399	3439	Top Lansing
3439	3483	Lansing
3483	3502	Lime
3502	3548	Lime
3548	3605	Lime
3605	3660	Lime
3660	3720	Cong.
3720	TD	
STATE OF INDIANA)	
County of Vanderburgh) SS:	

I, the undersigned, W. W. Keahey, Secretary-Treasurer, for Victor Drilling, Inc., do hereby certify that the above is a true and correct copy of the Driller's Log of formations for the above well.

Subscribed and sworn to before me, a Notary Public, in and for the said County in the State aforesaid this 11th day of Sept, 1953.

9-14-1953 W. W. Keahey
W. W. Keahey

9-24-56
My commission expires

Georgia Fischer
Notary Public

PLUGGING
FILE SEC 10 T 12 R 17W
BOOK PAGE 122 LINE 36