


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-21437-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Ellis County. Sec. 10 Twp. 12 Rge. 17 E/W
Location as "NE/CNW1SW1" or footage from lines

NE SW SE
Lease Owner Tsern Petroleum Co.
Lease Name HERMAN B Well No. #1
Office Address Box 486 - Ellinwood, Ks. 67526
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed February 23 19 78
Application for plugging filed Feb. 23 19 78
Application for plugging approved Feb. 23 19 78
Plugging commenced Feb. 23 19 78
Plugging completed Feb. 23 19 78
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3690
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Hole full of heavy mud to 550'-set plug with 70 sacks cement (50/50) pozmix thru drill p.
Middle Plug at 240' with 20 sacks cement thru drill pipe.

Top Plug at 40' with 1/2 sacks hulls and 10 sacks cement.

2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
2-28-1978
FEB 28 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc. -Great Bend, KS, 67530
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of Feb., 19 77

My commission expires April 11, 1978

Notary Public.

15-051-21437-00-00
DRILLERS' WELL LOG

DATE COMMENCED: February 17, 1978
DATE COMPLETED: February 23, 1978

Isarn Petroleum Co.
HEYMAN B-1
NE SW SE
Sec 10-T12S-R17W
Ellis County, Kansas

ELEVATION: 2153 KB

0 -	60'	Post Rock & Clay
60 -	710'	Shale
710 -	775'	Sand
775 -	788'	Shale
788 -	1010'	Shale & Sand
1010 -	1363'	Red Bed
1363 -	1405'	Anhydrite
1405 -	3122'	Shale & Lime
3122 -	3366'	Lime
3366 -	3370'	Shale
3370 -	3414'	Lime and Shale
3414 -	3690'	Lime, Shale, Chert
	3690'	RTD

FORMATION DATA

ANHYDRITE	1363
TOPEKA	3122
HEEHEER	3366
LANSING	3414
CONGLOMERATE	3670
RTD	3690

SURFACE PIPE: Set used 3-5/8",
28# at 251' with 150 sacks cement,
2 1/2 gal, 3 1/2 ch.cl.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this _____ day of February 1978

My Comm. Expires:
April 11, 1979

Alfred M. Hogue
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
2-28-1978
FEB 28 1978
CONSERVATION DIVISION
Wichita, Kansas