


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-051-20355-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

County. Sec. 11 Twp. 12S Rge. 17W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NW CS 8/7/09  
Lease Owner KATHOL. PETROLEUM, INC.  
Lease Name Rohleder Well No. 1  
Office Address 900 Sutton Place, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11/29/68 19  
Application for plugging filed 11/29/68 19  
Application for plugging approved 11/29/68 19  
Plugging commenced 11/29/68 19  
Plugging completed 11/29/68 19  
Reason for abandonment of well or producing formation No Zone with commercial value.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3670 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	2491	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 720' w/70 sx, set at 240' w/20 sx, set at 40' w/10 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KATHOL. PETROLEUM, INC.  
Address 900 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Homer J. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer J. Catt  
900 Sutton Place, Wichita, Kansas  
(Address)

to before me this 11th day of February 11, 19 69

Dixie Lee Brown  
Dixie Lee Brown Notary Public.



15-051-20355-00-00

KATHOL PETROLEUM, INC.

DRILLERS LOG

No. 1 ROHLER

SW NW NW Section 11-12S-17W

Ellis County, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Commenced: 11/19/68  
Completed: 11/29/68  
Elevation: 2123' KB

FROM	TO	FORMATION	REMARKS:	
0	50	Surface and Post Rock	Set 8-5/8" surface casing at 249' w/160 sx common cement.	
50	250	Shale		
250	1140	Shale & sand		
1140	1320	Shale & red bed	<u>SAMPLE TOPS:</u>	
1320	1364	Anhydrite		
1364	1970	Shale & shells		
1970	2130	Lime		
2130	3285	Lime & shale		Anhydrite 1320'
3285	3624	Lime		Heebner 3309 (-1186)
3624	3642	Conglomerate		Toronto 3330 (-1207)
3642	3670	Arbuckle		Lansing 3359 (-1236)
3670		R.T.D.		Base/K.C. 3591' (-1468)
				Cong. 3624 (-1501)
			Arbuckle 3643 (-1520)	
			TD 3670 (-1547)	

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

*Don Shawver*  
Don Shawver

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me this 10th day of February, 1969.

*Dixie Lee Brown*  
Dixie Lee Brown, Notary Public

Commission Expires: June 17, 1972

