


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-00361-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ellis County, Sec. 13 Twp. 12 Rge. 17 (E) W (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Fred J. Haynes  
Lease Name Kuhn Well No. 1  
Office Address Bldg. & Loan Bldg., Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed July 16 19 59  
Application for plugging filed " " 19 "  
Application for plugging approved " " 19 "  
Plugging commenced " " 19 "  
Plugging completed " " 19 "  
Reason for abandonment of well or producing formation No commercial production

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ~~XXXXXX~~ Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3757 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	212'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with mud, set plug at 550' and cemented with 20 sacks cement;  
filled hole with mud, set plug at 180' and cemented with 20 sacks cement;  
filled hole with mud, set plug at 40' and cemented with 10 sacks cement to surface.

**RECEIVED**  
STATE CORPORATION COMMISSION  
10-20-1959  
OCT 20 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Haynes Drilling Company  
Address Bldg. & Loan Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Darrell E. Haynes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Darrell E. Haynes  
Bldg. & Loan Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 59

My commission expires January 17, 1961

Ralph L. Schulte  
Notary Public.



15-051-00361-00-00

R

DRILLERS LOG

Kuhn # 1

SE SE NW 13-12-17

Ellis County, Kansas

Operator: Fred J. Haynes  
Bldg. & Loan Bldg.  
Russell, Kansas

Contractor: Haynes Drilling Company  
Russell, Kansas

Commenced: July 8, 1959

Completed: July 17, 1959

Casing: 8 5/8" at 212'w/110sks

I. P. - D & A

TOPS: Anhydrite 1330'  
Heebner 3349' -1198  
Toronto 3373'  
L-KC 3398'

Formation:

Clay & Post Rock	40
Shale	85
Shale & Shells	212
Shale	680
Shale & Sand	758
Sand	770
Shale & Sand	875
Sand	1020
Red Bed	1330
Anhydrite	1330-1367
Red Bed	1500
Shale & Shells	1960
Shale & Lime	2045
Lime	2485
Lime & Shale	2670
Lime & Shale	3115
Lime	3495
Conglomerate	3730
Arbuckle & TD	3757

I certify that the above is true and correct  
to the best of my knowledge.

Darrell E. Hoepner