

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-01195-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County. Sec. **14** Twp. **18S** Rge. **17** (E) (W)

Location as "NE/CNW/4SW 1/4" or footage from lines **C-SW 1/4 NE SW**

Lease Owner **Phillips & Hanson**

Lease Name **Miller** Well No. **#1**

Office Address **Union National Bank Bldg. Wichita, Kansas.**

Character of Well (completed as Oil, Gas or Dry Hole) **Dry hole**

Date well completed **12-19-50** 19 **50**

Application for plugging filed **12-19-50** 19 **50**

Application for plugging approved **12-19** 19 **50**

Plugging commenced **12-19** 19 **50**

Plugging completed **12-19** 19 **50**

Reason for abandonment of well or producing formation **Dry hole**

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes Verbal**

Name of Conservation Agent who supervised plugging of this well **Kidon Petty**

Producing formation Depth to top Bottom Total Depth of Well **3840** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
silt, shale & shells		0	130'	8 5/8"	178'	none
I.C. Line	Dry	3407	3640		none	none
Arbuckle	Dry	3820	3840		none	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred pits and filled hole with heavy mud. Placed bottom wood plug at 170', with 1 sack of Hulls on top of plug. Ran 15 sacks of well mixed cement through the drill pipe on same. Filled hole with heavy mud to 45'. Placed top wood plug and 1 sack of Hulls at 40', and ran 10 sacks cement through drill pipe filling hole to bottom of cellar.

12-20-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **Strain Drilling Company**
Hays, Kansas.

STATE OF **Kansas**, COUNTY OF **Ellis**, SS.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **[Signature]**

Box 188, Hays, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this **23rd** day of **December**, 19 **50**.

My commission expires **March 1, 1954**

Leroy R. Power
Notary Public.

22-7377-s 4-49-10M

PLUGGING
FILE SEC. **14** T. **18** R. **17**
BOOK PAGE **50** LINE **38**

15-051-01195-00-00
COMPANY: Phillips & Hanson

Lease: Miller #1

C-50 1/2 NE SW Sec. 14,
Twp. 12S, Rge. 17W,
Ellis County, Kansas.

Elevation: 2159 Derrick floor

0	130 Soil, shale & shells
130	178 Blue shale & shells
178	300 Shale & shells
300	700 Shale & shells
700	810 Hard white sand
810	1000 Sand
1000	1010 Shale
1010	1150 Shale
1150	1340 Redbed & shale
1340	1390 Anhydrite
1390	1460 Shale & redbed
1460	1790 Shale & shells
1790	1985 Shale & shells
1985	2050 Lime & shale
2050	2175 Lime & shale
2175	2295 Shale & lime
2295	2320 Lime & shale
2320	2405 Lime & shale
2405	2475 Lime & shale
2475	2575 Lime & shale
2575	2600 Lime & shale
2600	2660 Shale & lime
2660	2730 Shale & lime
2730	2800 Shale & lime
2800	3015 Shale & lime
3015	3120 Shale & lime
3120	3175 Lime & shale
3175	3235 Lime & shale
3235	3260 Lime & shale
3260	3310 Lime
3310	3360 Lime
3360	3410 Lime
3410	3465 Lime & shale
3465	3505 Lime
3505	3565 Lime
3565	3595 Lime
3595	3640 Lime
3640	3655 Lime & shale
3655	3695 Shale & lime
3695	3770 Shale (Cong.)
3770	3840 Lime
3840	T.D. (rotary bushings)

COMMENCED: 12- 7-50
COMPLETED: 12-19-50

CASINO RECORD:

a 5/8" Surface casing set at
178' w/125 socks cement by
Sun Cementing Co.

San Schlumberger Electric log
to total depth.

RECORDED
STATE COMMISSION
12-26-1950
DEC 26 1950
CO. OF RECORDS & INFORMATION
Wichita, Kansas

TOPS:

Anhydrite	1340	Arbuckle	3880
Redner	3363	T.D.	3940
Kansas City	3407		
Conglomerate	3879		

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Miller #1, located C-50 1/2 NE SW, Sec. 14, Twp. 12S, Rge. 17W, Ellis County, Kansas.

PLUGGING
FILE SEC 14 T 12 R 17 W
BOOK PAGE 50 LINE 31

Contractor: Strain Drilling Co.

By T.C. Strain
T.C. Strain.