

15-051-05476-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SE SE

SEC. 25 TWP. 12 RGE. 16

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Furthmeyer

Operator Southwest Grease & Oil Co Address 202 S Waterman Wichita, Kans

Field Fairport County Ellis

Total Depth 3345 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 694' circulated with cement - 5 1/2" at 3339' with
150 sax behind, Beker plugs to 3210', top perforations at
3095',

Filled with chat to 3090' set 4 sax cement with dump bailer,
pulled 2583' 5 1/2", filled with heavy mud to 250', set rock
bridge and 15 sax cement, filled with heavy mud to 35',
set rock bridge and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 25 T 12 R 16
BOOK PAGE 21 LINE 21

8-14-1950
[Signature]
District Conservation Agent
Date 8-12-50