

KANSAS
STATE CORPORATION COMMISSION
15-051-00326-00-00
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-1-1959
SEP 1 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: e Ellis

Location: NW NW NW Sec. 25 Twp. 12 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3441

I have this date completed supervision of plugging of:

Lease Name: Furthmeyer Well No. 1

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: same

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9AM Day 29 Month 8 Year 59

The above well was plugged as follows:

8 5/8" at 213' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 400', displaced

20 sax cement through drill pipe, heavy mud to 180', set cementing plug

and displaced 15 sax cement through drill pipe, heavy mud to 40', set

cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Signed: Jewel Letty
Conservation Division Agent

Reviewed: J Lewis Brock
Field Supervisor

Remarks: _____

INVOICED
DATE 1/5/60
INV. NO. 210-W