

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
15-051-20895-00-00  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
6-1-1973  
JUN 1 1973  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Bankoff Oil Company  
Complete Address Drawer 2479 Tulsa, Kansas  
Lease Name Miller Well No. 2  
Location NW SW NE Sec. 31 Twp. 12 Rge. (E) (W) 16  
County Ellis Total Depth 3545'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Woodman-Iannitti Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 1:30 P Day 27 Month 5 Year 1973

The above well was plugged as follows:

RTD 3545' 8 5/8 csg set at 222' cwc Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/1/73  
INV. NO. 7440-W

Signed: Rio J. Murray  
Well Plugging Supervisor