

KANSAS
15-051-20911-00-00
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
10-18-1973
OCT 18 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Producers, Inc.
Complete Address Shields Bldg., Russell, Kansas
Lease Name Windholz Well No. 1
Location SW SE SW Sec. 31 Twp. 12 Rge. (E) (W) 16
County Ellis Total Depth 3552'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 1 A Day 17 Month 10 Year 1973

The above well was plugged as follows:

RTD 3552' 8 5/8 csg set at 250' cwc 170 sk.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Masney
Well Plugging Supervisor

DATE 10/18/73
INV. NO. 8031-10