

15-051-20484-00-00

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 - 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Paramount Petroleum Co.

Complete Address Suite 102 5900 E. Central Wichita, Kansas

Lease Name Crisler CHRISLER Well No. 1

Location C S/2 N/2 SE Sec. 21 Twp. 12 Rge. (E) (W) 16

County Ellis Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Woodman & Iannitti Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:45A Day 28 Month 8 Year 1969

The above well was plugged as follows:

RTD 3500' 8 5/8 csg set at 197' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug, and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 20 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/3/69

INV. NO. 399-W

Signed: Leo F. Massey
Well Plugging Supervisor