

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

10-18-1976
OCT 10 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Bldg., Russell, Kansas 67665

Lease Name Dickinson Well No. 1

Location NE NW NE Sec. 29 Twp. 12 Rge. (E) (W) 16

County Ellis Total Depth 3615'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12 Day 14 Month 10 Year 1976

The above well was plugged as follows:

Total Depth 3615' 8 5/8 csg set 275' cwc 175 sk.

5 1/2 csg set 3609' cw 75 sk cem.

Filled 5 1/2 csg with sand (3615'-3575') dumped 5 sk cem W/dump bailer. (3575'-3540')

Cutoff & recovered A/3100' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs

hulls, 50 sk Comm Cem. 4% gel, displaced with 5 sk gel & water, & released 8 5/8 plug

& capped with 50 sk Comm Cem. 4% gel & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

DATE 10-18-76

Well No. 4001-W