

15-051-30295-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Solar Oil Co.

Complete Address: 1117 Union Natl Bldg. Wichita, Kansas

Lease Name Miller Well No. 1

Location SE-C-NW Sec. 29 Twp. 12 Rge. 16 (E) (W)

County Ellis Total Depth 3630

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: S&S Drilling Co. and Sun Cementing Co.

Address: Great Bend, Kansas License No. _____

Operation Completed: Hour 3 P Day 20 Month 5 Year 1966

The Above well was plugged as follows:

Total Depth 3630 8 5/8 set at 212 @w 160 sec Cem.

Gunned pits circulated hole with heavy mud, cementing plug at 910 ft..

and displaced 25 sac cement thru drill pipe, heavy mud to 210 ft., set

cementing plug and displaced 15 sac cement thru drill pipe, heavy mud to 30 ft.,

set cementing plug, 1/2 sac balls and 10 sac cement, cementing to base of collar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5-23-66
INV. NO. 2249-W

Signed: Leo Massey
Well Plugging Supervisor