

15-051-30416-00-00

KANSAS

Form CP-3  
Rev. 6-26-62

*R*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
1-16-1967  
JAN 16 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Circle Oil Company

Complete Address: 500 Bitting Building Wichita, Kansas

Lease Name Hall Well No. 1

Location NW NE NE Sec. 1 Twp. 12 Rge. 17 (E) (W) X

County Ellis Total Depth 3675

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sage Drilling Co.

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 11 A Day 12 Month 1 Year 1966

The Above well was plugged as follows:

RTD 3675' 8 5/8 csg set at 306' cwc 185 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc

cement thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cem.

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement

to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo M. [Signature]  
Well Plugging Supervisor

DATE 4606-W 1-16-67

INV. NO. 4606-W