

15-051-21410-00-00

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21,410 (of this well)

11-21-1977
NOV 21 1977
OFFICE OF THE
COMMISSIONER

Operator's Full Name F & M Oil Co., Inc.

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Dreiling Well No. 1

Location NW SE NE Sec. 9 Twp. 12 Rge. (E) (W) 17

County Ellis Total Depth 3383'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address License No.

Operation Completed: Hour 4:45 P Day 18 Month 11 Year 1977

The above well was plugged as follows:

RTD 3383' 8 5/8 csg set 256' cwc 150 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-22-77
INV. NO. 6233-W