

CONSERVATION DIVISION AGENT REPORT

API Number 15-051--22,985 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Zenith Exploration Partnership

Complete Address 1645 Court Place, Suite #320, Denver, Colorado 80202

Lease Name Rohleder Well No. #1

Location NE SE SW Sec. 9 Twp. 12 Rge. 17 (East) (West)

County Ellis Total Depth 3850'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Quanza Drilling Company

Address P. O. Box 1309, Bethany, Oklahoma 73008 License No. \_\_\_\_\_

Operation Completed: Hour: 9:00 AM Day: 17th Month: May Year: 19 82

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-385' s.p. cuc. w/240 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 310' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated 10 sacks of cement in rat hole.

Amount of Surface Casing: 385' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1982  
5-24-1982  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED  
DATE 6-3-82  
388-w