

15-051-00489-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 94-37

LOCATION NE SW SW

SEC. 9 TWP 12 RGE. 17

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Rohleder

Operator Carl Lebsack Address Hays, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3520 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" at 3520' with  
100 sax cement behind - perforated at ~~3470~~ 3486'.

Filled with sand to 3470', set 4 sax cement with dump  
bailer- pulled 2950' 5 1/2' - filled with mud to 180', set  
rock and 15 sax cement, mud to 35', set rock and 10 sax  
cement to bottom cellar.

District Conservation Agent

Date 2-11-55

2-14-1955

**PLUGGING**  
FILE SEC 9 T 12 R 17W  
BOOK PAGE 94 LINE 37