

15-051-00259-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 8-20

LOCATION NW NW NW

SEC. 9 TWP. 12 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Roth \_\_\_\_\_

Operator Bennett & Roberts Address Box 633 Russell, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3675 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 197' circulated with cement - 5 1/2" at 3048' with 50  
sax cement behind.

Filled with sand to 3630', set 4. sax cement with dump bailer,  
pulled 3275' 5 1/2" - filled hole with heavy chunk mud to 220', set  
rock and 20 sax cement, heavy mud to 35', set rock and 10 sax  
cement to 0'.

*Edward Kelly*  
District Conservation Agent

Date 4-30-57

STATE COMMISSION  
5-7-1957  
MAY 7 - 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 9 TWP. 12 R. 17W  
BOOK PAGE 8 LINE 20