

K

Form CP-3  
Rev. 6-4-68

KANSAS  
15-051-21371-00-00  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10-3-1977  
OCT 03 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 051- 21,371 (of this well)

Operator's Full Name John O. Farmer, Inc.

Complete Address Box 352, Russell, Kansas

Lease Name Chrisler Well No. 1

Location 100' NE of SW SW NE Sec. 21 Twp. 12 Rge. (E) (W) 16

County Ellis Total Depth 3480'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 9:45 P Day 30 Month 9 Year 1977

The above well was plugged as follows:

~~RTD 3480'~~ 8 5/8 csg set 216' cwc 140 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 10-3-77

INV. NO. 5935-W

Signed: Geo Massey  
Well Plugging Supervisor