

15-163-30148-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1973
CONSERVATION DIVISION
Wichita, Kansas
06-01-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum, Inc.

Complete Address R. R. # 2 Great Bend, Kansas 67530

Lease Name Tucker "G" Well No. 1

Location App. SE SW NW Sec. 7 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3868'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn Casing Pulling

Address Box 156 Ellinwood, Kansas 67526 License No. 686

Operation Completed: Hour 9:30 A Day 29 Month 5 Year 1973

The above well was plugged as follows:

Total depth 3868' 8 5/8 csg set at 212' cwc 175 sk.

5 1/2 csg set at 3866' cw 125 sk cmt. Top of cement 3414'.

5 1/2 csg PBTD 3859 1/2 with top perf. (3815')

Filled 5 1/2 csg with sand (3800-3859 1/2) dumped 5 sk cmt W/dump bailer. (3765-3800)

Cutoff and recovered 2141' of 5 1/2 csg.

Pumped down 8 5/8 csg with 22 sk gel & water W/500 lbs hulls -70 sk cmt -10 sk

gel & water -released 8 5/8 plug and pumped 50 sk cmt by Sun Cementing Co.

Max pres. 350 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Reo F. Mussey
Well Plugging Supervisor

INVOICED

DATE 6/1/73

INV. NO. 7435-W