

KANSAS  
STATE CORPORATION COMMISSION

15-163-03578-0001

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

FILED  
STATE CORPORATION COMMISSION  
9-7-61  
SEP 7 1961  
CONSERVATION DIVISION  
KANSAS

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks

Location: SW SW NE Sec. 7 Twp. 10 Rge. (E) (W) 20

Name of Field: \_\_\_\_\_ Total Depth: 3856

I have this date completed supervision of plugging of:

Lease Name: Sauer Well No. 2

Operator's Full Name: Noah & Gill

Complete Address: Box 1038 Wichita (1) Kansas

Plugging Contractor: same & Globe Cementing Co

Address: Same License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: wash down old hole

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No ☒

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5:30 PM Day 4 Month 9 Year 61

The above well was plugged as follows:

8 5/8" 155' circulated with cement - 5 1/2" 3852'

Run 2" tubing to 3800', circulated hole with heavy gel mud through 2" tubing - pulled 581' 5 1/2" to 480', recirculated hole with heavy mud through 5 1/2" at 480' ( 60 sax gel in hole ), pumped plug and 25 sax cement at 480' - heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: Edon Petty  
Conservation Division Agent

Reviewed: Harold Hallis  
Field Supervisor

Remarks:

INVOICED

DATE: 9/22/61

INV. NO. 3425-W