

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,689-0000 (of this well)

4-11-77
APR 11 1977

Operator's Full Name Petroleum, Inc.

Complete Address 800 R. H. Garvey Bldg., Wichita, Kansas

Lease Name Temple "B" Well No. 4

Location SE SW SW Sec. 7 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3795'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor John O. Farmer Drlg.

Address Russell, Kansas License No.

Operation Completed: Hour 2:30 A Day 9 Month 4 Year 1977

The above well was plugged as follows:

RTD 3795' 8 5/8 csg set 244' cwc 170 sx. Flg Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-11-77

INV. NO. 4954-W