

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 11 100-41 Location: SW SW NE

County: Rooks Sec. 7 Twp. 10 Rge. 20 (E) (W)

Name of Field or Pool: _____ Total Depth: 5856

I have this date completed supervision of plugging of:

Well No. 1 Lease Sauer

Operator's Full Name John O. Farmer Inc

Complete Address: Russell, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 7PM Day 24 Month 5 Year 58

The above well was plugged as follows:

8 5/8" at 155' circulated with cement - 5 1/2" 3852 with 150 sax cement
behind and squeezed with cement at 900'
Filled with sand to 3840', set 4 sax cement with dump bailer, started
580' 5 1/2" - circulated hole with heavy mud at 550' through 5 1/2" -
displaced 20 sax cement through ~~5 1/2"~~ 5 1/2" at 550' - heavy mud to 150',
displaced 15 sax cement through 5 1/2" - heavy mud to 35', set rock and
10 sax cement to bottom cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Edson Leary*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
6-2-58

JUN 2 1958

Reviewed: *J. Lewis Brock* Signed: _____
Field Supervisor Well Plugging Supervisor

Remarks:

PLUGGING
FILE SEC 7 T. 10 R. 20W
BOOK PAGE 100 LINE 41