

15-163-00295-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

12-6-61
CONSERVATION DIVISION

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: SE SE NW Sec. 7 Twp. _____ Rge. 10 (E) _____ (W) 20

Name of Field: _____ Total Depth: 3865

I have this date completed supervision of plugging of:

Lease Name: Holmes Well No. 1

Operator's Full Name: J. O. Farmer Inc

Complete Address: Russell, Kansas

Plugging Contractor Ace Pipe Pulling Inc

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 2 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 160' circulated with cement - 5 1/2" 3859' with 50 sax cement.
Filled with sand to 3840', set 4 sax cement with dump bailer, pulled
1190' 5 1/2" to 550', circulated hole with heavy mud (13sax Gel), displaced
20 sax cement through 5 1/2" at 500', heavy mud to 170', displaced 20 sax
cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.
Mudding and cementing by Ace Pipe Pulling Pump Truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 12/12/61
INV. NO. 4164-4