

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 93-36

LOCATION NW NW SE

SEC. 7 TWP. 10RGE. 20W

Dry Hole \_\_\_\_\_ Abandoned Oil Well <sup>X</sup> \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Sauer

Operator Co-op Refg Assn Address Box 765 Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3850 Feet.

Plugging Contractor Betts Oil Field Service

Plugging Contractor's License No. 70

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 197' circulated with cement - 5 1/2" at 3855' with  
75 sax cement behind.

Filled with chat to 3845', set 4 sax cement with dump bailer,  
pulled 2080' 5 1/2" - filled with mud to 195', set rock and 15 sax  
cement & mud to 35' set rock and 10 sax cement to bottom cellar.

*E. J. [Signature]*  
District Conservation Agent

Date 2-22-55

**PLUGGING**  
FILE SEC 7 T 10 R 20W  
PAGE 93 LINE 36

RECEIVED  
2-26-55  
FEB 26 1955