

15-163-00439-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8-5-63
AUG 5 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Co
Complete Address: 1130 Wichita Plaza Wichita, Kansas
Lease Name Veatch Well No. 2-B
Location SW NW NE Sec. 9 Twp. 10 Rge. (E) (W) 20
County Rooks Total Depth 3822
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kansas License No. 399
Operation Completed: Hour 2PM Day 1 Month 8 Year 63

The Above well was plugged as follows:

8 5/8" 141' circulated with cement - 5 1/2" 3795' with 100 sax cement & squeezed in Dakota section - amount cement ?
Filled with sand to 3780', set 4 sax cement with dump bailer - pulled 795' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550', displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180' displaced 25 sax cement through 5 1/2" at 180', heavy mud to 30', cement to bottom cellar.

Mudding and cementing by Southwest Pump Truck.

I hereby certify that the above well was plugged as herein stated.

DATE 8/5/63
INV. NO. 7515-W

Signed: [Signature]
Well Plugging Supervisor