

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SW SW

SEC. 9 TWP. 10 RGE. 20W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease \_\_\_\_\_ Rode 817 Union Nat'l Bldg Bldg

Operator Okmar Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 5828 Feet.

Plugging Contractor R & S Pipe Pulling Co

Plugging Contractor's License No. 1

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 187' circulated with cement - 5 1/2" at 5791' with 125 sax  
cement behind.

Sand to 5730' set 4 sax cement with dump bailer, pulled 3000'  
5 1/2", mud to 180', set rock and 15 sax cement, mud to 35', set  
rock and 10 sax cement to bottom cellar.

RECORDED

3-29-54

Edna Petty  
District Conservation Agent

Date 3-27-54

**PLUGGING**  
FILE SEC 9 T 10 R 20W  
BOOK PAGE 23 LINE 24