

15-163-00604-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 8 Twp 10 Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines SW SE SW

Lease Owner Cooperative Refinery Association

Lease Name Wanker "B" Well No. 1

Office Address Box 765, Great Bend

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-27-52 19

Application for plugging filed 10-29-52 19

Application for plugging approved 10-29-52 19

Plugging commenced 10-27-52 19

Plugging completed same day 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3902 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled T.D. 3900' Plugged to 200'
set plug, cemented drill pipe
15 sx & filled mud 30' from top
set plug & cemented 10 sx to top
surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker Drilling Co.
Address 2008 Lakin, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
L. M. Collins (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L M Collins
Cooperative Refinery Association (Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1952

Marjorie Alice Dabbs Notary Public.

My commission expires 9-15-56

24-2675-S 2-52-20M

PLUGGING
FILE SEC 8 T 10 R 20
BOOK PAGE 53 LINE 13

11-11-52
NOV 17 1952
CONSERVATION DIVISION
WICHITA, KANSAS

15-163-00604-0000

COOPERATIVE REFINERY ASS'N.

Great Bend, Kansas

DRILLERS LOG

Wanker B-1
Sec: 8-10s-20W
Loc: SW SE SW
Rooks County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Honaker Drilling Co.

Comm: 10-15-52
Comp: 10-27-52
Casing: 8-5/8" 215'
Production: D&A

0	15	Top soil and clay	
15	70	Sand	
70	165	Sand & shale	
165	215	Shale	
215	1450	Shale & shells	
1450	1690	Red Bed & shale & shells	
1690	1755	Shale & shells	
1755	1790	Anhydrite	Cemented 8-5/8" casing at
1790	2260	Shale & shells	215 ft. with 125 sacks
2260	2375	Lime & shale	cement. 1 sack calcium chloride.
2375	2505	Lime, Salt & shale	
2505	2675	Shale & lime	
2675	2860	Lime- Shale & shells	
2860	2945	Shale & shells	
2945	2960	Lime	
2960	3020	Shale & Lime	
3020	3325	Lime & shale	
3325	3804	Lime	
3804	3887	Conglomerate	
3887	3902	Lime T.D.	

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

L M Collins

Subscribed and sworn to before me this 6th day of November 1952

Margorie Alice Doherty
Notary Public



PLUGGING
FILE SEC 8 T 10 R 2024
BOOK PAGE 55 LINE 13

