

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

WELL NUMBER 5-163-23,318-0000

LEASE NAME Williams "B"

WELL NUMBER 4  
1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 8 TWP. 10S RGE. 20W XX or (W)

COUNTY Rooks

Date Well Completed 4/28/01

Plugging Commenced 7:30AM 4/28/01

Plugging Completed 10:15AM 4/28/01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR THE DANE G. HANSEN TRUST

ADDRESS P.O. Box 187 Logan, KS 67646

PHONE (785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/26/01 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.O. 3826

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	210	8 5/8	210.15	None

RECEIVED

5-21-01  
MAY 21 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
1st Plug @ 1775' W/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes with 48Vis Mud.  
2nd Plug @ 1000' W/100sks 15sks In Rat Hole Plugs displaced with mud.  
3rd Plug @ 260' W/40sks Total 200sks 60/40Poz 6%Gel W/1#FC/sk By Allied Cementing  
4th Plug @ 40' W/10sks Completed @ 10:15Am 4/28/01

Name of Plugging Contractor Discovery Drilling Co., Inc./ License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: THE DANE G. HANSEN TRUST

STATE OF Kansas COUNTY OF Phillips, ss.

Dane G. Bales

(Employee of Operator) or ~~Operator~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Dane G. Bales

Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 18 day of May, 2001

My Commission Expires: July 17, 2004  
Betty Jane Bittel Notary Public



Form CP-  
Revised 05-8

OR