

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02030-0000

API NUMBER Drilled June 1954

LEASE NAME Oesterreich

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 8 TWP. 10 RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed June 1954

Plugging Commenced 11/22/00

Plugging Completed 11/22/00

RECEIVED

DEC - 4 2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

RICHARD L. WALLGREN, SR.
Operator for The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, KS 67646

PHONE# (785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 22, 2000 (date)

by Card Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3807 Bottom 3824 T.D. 3824

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	152'	None
				5 1/2	3814	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Started 2 sxs. Hulls and 12 yds of 5 sxs. cement per yard and
33,000 # Sand per yard. Displaced down casing till casing and
collar was full.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B & B Redi Mix, Inc. License No. 12-5-00

Address P. O. Box 513, Stockton, KS 67669

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust CONSERVATION DIVISION

STATE OF Kansas COUNTY OF Phillips, ss.

Richard L. Wallgren, Sr. (Employee of Operator) or (Operator) of
above-described well, being first July sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Richard L. Wallgren, Sr.
P. O. Box 187, Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 4th day of December 2000



My Commission Expires: July 17, 2004 Betty Jane Bittel Notary Public

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Oesterreich #1
 LOCATION SE SE NE, Sec. 8-10S-20W, Rooks
 POOL NAME _____ COUNTY ROOKS STATE KANSAS
 COMMENCEMENT DATE June 17, 1954 COMPLETION DATE June 25, 1954

LOG OF WELL

Elevation: 2251 R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	152	Shale		
152	800	Shale		
800	1220	Shale-Sand		
1220	1460	Sand		
1460	1675	Red Bed	0° - 1500'	
1675	1740	Red Bed		
1735	1775	Anhydrite		
1775	2060	Shale-Shells	0° - 2000'	
2060	2350	Lime-Shale		
2350	2565	Lime-Shale	0° - 2500'	
2565	2685	Lime-Shale		
2685	2925	Lime-Shale		
2925	3025	Lime-Shale	0° - 3000'	
3025	3200	Lime-Shale		
3200	3326	Lime-Shale		
3326	3405	Lime-Shale		
3405	3485	Lime-Shale		
3485	3540	Lime-Shale	0° - 3500'	
3540	3585	Lime-Shale		
3585	3609	Lime-Shale		DST 3599-3609
3609	3650	Lime-Shale		
3650	3710	Lime		
3710	3764	Lime-Shale		
3764	3816	Lime-Shale		
3816	3824	Lime-Shale		DST 3814-3824

CASING LEFT IN HOLE AFTER COMPLETION

Ran 152.42' of 8-5/8" Surface Casing (5 jts).
 Ran (119 jts) 3820.39 5-1/2" OD Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

~~WILLIAMS CO.~~

By Vicky Jacobs
 Office Manager

Subscribed and sworn to before me this 28th day of June, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

DEC 5 2000

CONSERVATION DIVISION
 Wichita, Kansas

MANAGER
 1954