

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-03315-0000

API NUMBER 3-4-51

LEASE NAME Hinkhouse

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 10S RGE. 20 (S) or (W)

COUNTY Rooks

Date Well Completed 4-3-51

Plugging Commenced 2-17-89

Plugging Completed 2-24-89

LEASE OPERATOR Griggs Oil, Inc.

ADDRESS 107 N. Market - Ste. 800, Wichita, KS 67202

PHONE# (316) 267-7779 OPERATORS LICENSE NO. 5058

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-16-89 (date)

by Marion Schmidt Gilbert Balthazor (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation Arbuckle/Granit Wash Depth to Top 3918' Bottom 4293' T.D. 4293'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

3-14-89

MAR 14 1989

Formation	Content	From Surface	To	Size	Put in	Pulled out
		Surface	162'	8-5/8"	162'	-0-
		Surface	3918'	5-1/2"	3918'	-0- CONSERVATION DIVISION
		Surface	1563'	2-1/2"	1563'	1311' Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran 2" tubing to 1290' mix 100sks common cement. Followed with 300 sks 60-40 pos 8% gel partial circ. After mixing 300 sks cement - did not circ to surface. Reorder 250 sks 60-40 pos 8% gel mis 150 sks 3 sks hulls on vac. shut down 30 min. Mix 100 sks on vac. after mixing. Shut down wire on 2-20-89. 754' top cement (See back of form)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Griggs Oil, Inc. (B.J. Titan Services) License No. 5058

Address 107 N. Market - Ste. 800, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Griggs Oil, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wilber D. Berg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) 107 N. Market - Ste. 800, Wichita, KS

67212

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 89

Melinda K. Schultz
 Notary Public

My Commission Expires: July 16, 1989

2-24-89

Ran 2-1/2" tubing to 725'. Mix 95 sks 60-40 pos .8% gel, 1 sack hulls
Circ. cement to surface. Laid down tubing - pumped 30 sks down 5-1/2"
to fill casing.