

15-163-03077-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County, Sec. 9 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW%SW%" or footage from lines N/2 N/2 SW/4

Lease Owner Okmar Oil Company, et al

Lease Name Rode Well No. 6

Office Address 817 Union National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 13, 19 55

Application for plugging filed (verbal) December 13, 19 55

Application for plugging approved (verbal) December 13, 19 55


Plugging commenced December 13, 19 55

Plugging completed December 13, 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	None	0	186'	8 5/8"	186'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 180'
Set bottom plug at 180' with 15 sacks cement and 1/2 sack Hulls
Filled hole to 40' with mud. Set top plug at 40' with 10 sacks cement and 1/2 sack Hulls

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.

Address 510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Robert F. Walters

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters

510 Orpheum Building, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 55

Pauline Rudolph

Notary Public.

My commission expires March 10, 1956

PLUGGING
FILE SEC 9 T 10 R 20W
BOOK PAGE 25 LINE 45

12-22-55

RODE NO. 6

Location:	N/2 N/2 SW/4 Sec. 9-10S-20W Rooks County, Kansas	Date Spudded:	12-1-55
Operator:	Olinar Oil Company	Completion:	12-13-55
Contractor:	Walters Drilling Co.	Elevation:	2236 Gr 2239 DF 2241 KB
Surface Casing:	8 5/8" set at 186' with 125 sacks cement and 1 Gal. Chloride		
Oil String:	None. D & A		

L O G

(Figures indicate bottom of formation)

Surface	0 to 186'
Shale and Shells	1200
Sand	1405
Shale and Shells	1726
Anhydrite	1765
Shale and Shells	2418
Lime and Shale	3570
Lime	3740
Lime and Shale	3850
Total Depth	3850

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By Robert F. Walters

Subscribed and sworn to before me
this 16th day of December, 1955.

Pauline Hudickson
Notary Public

My commission expires:
March 10, 1956

PLUGGING
FILE SEC 9 T 10 R 20W
BOOK 25 LINE 45

RECEIVED
NOV 25 1955
CONSERVATION DIVISION
WICHITA, KANSAS