


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 9 Twp. 10 Rge. 20 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW NW NE
Lease Owner Okmar Oil Co.
Lease Name Veatsch "B" Well No. #2
Office Address 820 Union National Center Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7-30-63 19
Plugging completed 8-1-63 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3780', mixed and ran 5 sacks cement thru dump bailer.
Circulated hole with 7 sacks gel and spotted 20 sacks cement at 550'. Pulled 11 joints. Spotted 25 sacks cement at 180'. Pulled 6 joints. Mudded hole to 40' - set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
8-5-63
AUG 5 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. [Signature] Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of August, 1963
My commission expires 24 October 1964
[Signature] Notary Public.

15-163-00439-0000

W/2 NE/4 SW/4 Sec. 9-102-437
 Reno County, Kansas

Date Drilled: 11-17-49
 Rotary Company: 11-17-49
 Total Depth: 3796'
 Elevation: 2217 KB

Operator: Heathman Drilling Co., Inc.
 Contractor: Heathman Drilling Co., Inc.

Surface Casings: 5 jts. 8-5/8" (141.21' thds. off)
 set at 141' w/115 sacks cement.

Oil Strings: 75 jts. 5 1/2" (3807'-16) cemented
 1' off bottom with 100 sacks cement.
 @ 3795'

RECEIVED
 STATE CORPORATION COMMISSION

JUL 17 1963

CONSERVATION DIVISION
 Wichita, Kansas

TOPS KB

Anhydrite	1714 (+513)
Haebner	3457 (-1230)
Lansing-K.C.	3495 (-1268)
Base-K.C.	3717 (-1190)
Conglomerate	3744 (-1517)
Simpson	3784 (-1547)
Arbuckle	3793 (-1566)
Rotary T.D	3796

LOG

Sand shale	0	to	141
Shale			695
Sand			780
Shale			850
Sand			985
Shale			1010
Shale and shells			1200
Sand			1445
Shale and red rock			1714
Anhydrite			1758
Shale and shells			2310
Shale and lime			3520
Lime			3699
Lime and shale			3756
Chert and conglomerate			3785
Shale and lime cherty			3796
Total Depth			3796'

Drilling - In.

Drilled plug @ 3796; hole filled
 250' oil in 30 min. - drilled
 deeper to 3799' - swabbed 2 bbls
 - 10 hrs - gave 500' - swabbed
 6 bbls 4 hrs - P O P

The undersigned, Heathman Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN DRILLING CO., INC.

BY: [Signature]

Subscribed and sworn to before
 me this 12th day of December 1949.

[Signature]
 Notary Public

My commission expires: June 28, 1952