

15-163-03396-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 9 Twp. 10S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines NW 1/4 SE 1/4 SE 1/4
Lease Owner Barnett Oil Company
Lease Name Hinkhouse Well No. 3
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 30, 1952
Application for plugging filed December 30, 1952
Application for plugging approved December 30, 1952
Plugging commenced December 30, 1952
Plugging completed December 30, 1952
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3767 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8 5/8"	118 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3767 feet to 118 feet. Set wooden plug at 118 feet and filled surface casing with 1/2 sack of hulls and 15 sacks of cement to 71 feet. Filled casing with heavy mud from 71 feet to 40 feet. Set wooden plug at 40 feet and filled surface casing with 1/2 sack of hulls and ten sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address 623 First Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *W. R. Hunter*
417 First Nat'l Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1953

My commission expires February 27, 1956.

Mildred F. Willis
Notary Public.

24-2675-5 2-52-20M



PLUGGING
FILE SEC 9 T 10 R 2024
BOOK PAGE 70 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
1-6-53
JAN 6 - 1953
CONSERVATION DIVISION
KANSAS

15-163-03396-0000

BARNETT OIL COMPANY
LOG OF HENKHOUSE WELL NO. 3
NW 1/4 SE 1/4 SE 1/4 SECTION 9-10S-20W
ROOKS COUNTY, KANSAS

DATE COMMENCED: December 17, 1952

DATE COMPLETED: December 30, 1952

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	-0-	35	
Sand	35	42	
Shale and Shells	42	1200	Set 8 5/8" Surface Pipe at 118 feet; cemented with 125 sacks of cement.
Sand	1200	1350	
Shale and Shells	1350	1615	
Anhydrite	1615	1675	
Shale and Shells	1675	1730	
Shale	1730	1835	
Shale and Shells	1835	2200	
Shale	2200	2265	
Shale and Lime	2265	2800	
Lime	2800	2850	
Lime and Shale	2850	3205	
Lime	3205	3680	
Lime and Shale	3680	3767	
Total Depth		3767	Dry and Abandoned

PLUGGING
FILE SEC 9 T 10 R 20
BOOK PAGE 20 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1953
CONSERVATION DIVISION
Wichita, Kansas