

BRIDGEPORT OIL COMPANY, INC.
918 Central Building,
Wichita 2, Kansas.

Well Log-----Hinkhouse "B" #1
SE SW SE 9-10S-20W
Rooks County, Kansas

Elevation-----2186'
Date Started-----6-28-45
Date Completed----7-13-45

Casing Record:--
8-5/8" Casing Cemented @ 210'
with 125 sacks bulk cement.

Rotary Tools-----0 to 3850

<u>LOG</u>	
0	210 Shale & Shells
210	500 Shale
500	735 Sandy Shale
735	1025 Shale & Shells
1025	1080 Sand
1080	1285 Shale & Shells
1285	1400 Sand & Shells
1400	1535 Shale
1535	1555 Sandy Shale
1555	1715 Shale, Lime & Shells
1715	1900 Shale & Shells
1900	2084 Shale
2084	2295 Lime & Shale
2295	2395 Shale
2395	2510 Lime & Shale
2510	2570 Shale & Lime Shells
2570	2720 Lime & Shale
2720	2789 Shale & Lime Shells
2789	2910 Lime & Shale
2910	2975 Shale
2975	3050 Lime & Shale
3050	3100 Shale
3100	3235 Shale & Lime Shells
3235	3300 Lime & Shale
3300	3351 Lime
3351	3395 Lime & Shale
3395	3705 Lime
3705	3735 Lime & Shale
3735	3771 Lime
3771	3773 Chert
3773	3800 Cherty Conglomerate
3800	3816 Conglomerate & Shale
3816	3850 Conglomerate
3850	T.D.

Plugged & Abandoned 7-13-45

<u>Formation Tops -DF</u>	
Top Anhydrite	1655'
Top Winfield	2320'
Top Ft. Riley	2390'
Top Base Reford	2550'
Top Topeka	3240'
Top Heebner	3431'
Top Base Oread	3465'
Top Lansing	3474'
Top Conglomerate	3765'
Top Simpson	3805'
Top Arbuckle	3814'

I, Frank Leach, do hereby certify that the above log is correct to the best of my knowledge and belief.

BRIDGEPORT OIL COMPANY, INC.

By Frank Leach

FILE
BOOK
9 10220W
21 1219