

15-051-20355-00-00

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Kathol Petr. Co. & Chief Drlg. Co.

Complete Address: 900 Sutton Place Wichita, Kansas

Lease Name Rohleder Well No. 1

Location SW NW NW Sec. 11 Twp. 12 Rge. 17 (E) (W) XX

County Ellis Total Depth 3670'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Chief Drlg.

Address: Box 797 Great Bend, Kansas License No.     

Operation Completed: Hour 7P Day 28 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3670' 8 5/8 csg set at 249' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mearns  
Well Plugging Supervisor

DATE 12/3/68

INV. NO. 8930-w