

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Company Inc.

Complete Address: 1425 Wichita Plaza Wichita, Kansas 67202

Lease Name Hall Well No. 1

Location SE SW SE Sec. 11 Twp. 12 Rge. 17 (E) (W) X

County Ellis Total Depth 3728

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 11:50 Day 3 Month 5 Year 1967

**The Above well was plugged as follows:**

RTD 3728' 8 5/8 csg set at 218' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 5/5/67

INV. NO. 5167-W

**RECEIVED**  
STATE CORPORATION COMMISSION

5-5-1967  
MAY 5 1967

Signed: Leo F. Massey  
Well Plugging Supervisor

CONSERVATION DIVISION  
Wichita, Kansas