

15-051-~~5100~~<sup>19264</sup>-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 128-25  
LOCATION SE SE SE  
SEC. <sup>11</sup> 11 TWP. 12 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. M-1 Lease Hall

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 5690 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 505' circulated with cement - 5 1/2" at 5592 with  
100 sax cement behind, perforations at 5507'.  
Filled with chat to 5280', set 4 sax cement with dump  
bailer, pulled 300' 5 1/2", filled hole with mud to 300', set  
rock bridge and 15 sax cement, filled with mud to 55', set  
rock and 10 sax cement to bottom cellar.

RECEIVED  
1-2-1952  
JAN - 2 1952  
CONSERVATION DIVISION  
WICHITA, KANSAS

District Conservation Agent  
Date 12-25-51

**PLUGGING**  
FILE SEC 11 TWP 12 RGE 17  
BOOK PAGE 127 LINE 25