

15-051-20836-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
7-25-1972  
JUL 25 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Company

Complete Address 800 Bitting Bldg., Wichita, Kansas

Lease Name Schmeidler Well No. 1

Location SW SE SE Sec. 16 Twp. 12 Rge. (E) (W) 17

County Ellis Total Depth 3746'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Gabbert & Jones (Rotary)

Address Wichita, Kansas License No.       

Operation Completed: Hour 12 M Day 22 Month 7 Year 1972

The above well was plugged as follows:

RTD 3746' 8 5/8 csg set at 212' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Boyd Mearns  
Well Plugging Supervisor

INVOICED

DATE 7-28-72

INV. NO. 6072-10