

15-051-20534-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corp.

Complete Address Suite 1000 Century Bldg., Wichita, Kansas

Lease Name Schmeidler "A" Well No. 1

Location SE SW NW Sec. 22 Twp. 12 Rge. (E) (W) 17

County Ellis Total Depth 3685

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Drlg.

Address Victoria, Kansas License No.

Operation Completed: Hour 7:15 A Day 22 Month 11 Year 1969

The above well was plugged as follows:

BTD 3685' 8 5/8 csg set at 248' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 275' set cementing plug and displaced 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellae.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/20/69
INV. NO. 922-U

Signed: Leo A. Mandy
Well Plugging Supervisor