

KANSAS

Form CP-3
Rev. 6-26-62

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-051-20114-00-00

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1967
08-06-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bank Bldg. Wichita, Kansas

Lease Name Jensen Well No. 1

Location NW NE SE Sec. 34 Twp. 12 Rge. 18 (E) (W) X

County Ellis Total Depth 3097

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 7 P Day 2 Month 9 Year 1967

The Above well was plugged as follows:

RTD 3097' 8 5/8 csg set at 215' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 745' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo T. Messy
Well Plugging Supervisor

DATE 9/7/67
INV. NO. 6293-W