

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-051-20740-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address 435 PAGE COURT - 220 W. DOUGLAS
1425 WICHITA PLAZA WICHITA, KANSAS 67202

Lease Name Dumler Well No. 1

Location NW SE NW Sec. 33 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Teels

Address License No.

Operation Completed: Hour 8:30 A Day 24 Month 8 Year 1971

The above well was plugged as follows:

RTD 3800' 8 5/8 csg set at 242' cwc Cmt. Mat. 50-50 pez W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. J. Murray
Well Plugging Supervisor

M. BOEH ON ANI
12-01-6 S W C