

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1975
04-01-1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-051-01241-00-01

Operator's Full Name The Pyramid Corporation

Complete Address Suite 110, 3000 W. Kellogg Dr., Wichita, Kansas 67213

Lease Name Jensen "B" Well No. 1 -OWVO

Location NE NW SE Sec. 34 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3745'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 3 P Day 27 Month 3 Year 1975

The above well was plugged as follows:

- Total Depth 3745' 8 5/8 csg set 209' cwc 150 sk.
- 4 1/2 csg set 3742' cw 165 sk cem.
- 4 1/2 csg PBSD 3430' with top perf. (3381')
- Filled 4 1/2 csg W/snd (3430-3350) dumped 3 sk cem W/dump bailer. (3350-3320)
- Cutodd & recovered 20 jts. A/640' of 4 1/2 csg.
- Mixed & pumped down 8 5/8 csg with 25 sk gel & water W/100 lbs hulls -released
- plug & 120 sk 50-50 poz 6% by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 4/1/75
INV. NO. 1082-W