

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

04658
15-051-~~04658~~-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1963
09-03-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Crescent Oil & Gas

Complete Address: Box 485 Ellinwood, Kansas

Lease Name Gorrell Well No. 1

Location NW NW NW Sec. 16 Twp. 12 Rge. (E) (W) 19

County Ellis Total Depth 3830

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drg Co

Address: Wichita, Kansas License No.

Operation Completed: Hour 4PM Day 26 Month 8 Year 63

The Above well was plugged as follows:

8 5/8" 262' circulated with cement.

Circulated hole with heavy mud, set plug at 600', displaced 20 sax
cement through drill pipe, heavy mud to 210', set plug and 20 sax
cement, heavy mud to 35', set plug, 1/2 sack hulls and filled to
bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

DATE 8/30/63
INV. NO. 9674-U

Signed: [Signature]
Well Plugging Supervisor