

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -05/-21,781-00-00 (of this well)

Operator's Full Name KANSAS OIL CORPORATION

Complete Address 400 NORTH WOODLAWN - WICHITA, KANS. 67208

Lease Name WANN + HARWOOD Well No. #2

Location C-5 1/2 - NE - NE Sec. 21 Twp. 12 Rge. 19 (E) (W) W

County ELLIS Total Depth 3749 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor MIDWEST CASING PULLING

Address BOX F. SUBLETTE, KANS. 67877 License No. 966

Operation Completed: Hour 10:15 ^{AM} Day 30 Month JULY Year 1980

The Above well was plugged as follows:

8 5/8" 254 FE SP. CUC w/185 ST CMT. -> 4 1/2" SET AT 3750 FE
PERF'S 3550'-52' -> 3529'-31' -> 3512'-14' -> BRIDGE PLUG AT 3270'
PERF'S 3234'-40' - BOTTOM PLUGGED WITH 2 ST HULLS + 10 ST CMT PUMPED IN.
SHOT PIPE @ 2514 FE + 2311 FE - RECOVERED 2311 FE
ORDERED 140 ST 50/50 PORMIX 6% GEL - 11 ST GEL. + 5 ST HULLS + 8 5/8" Plug
PUMPED IN WITH PUMP TRUCK.
PUT IN - 3 ST HULLS - 6 ST GEL. - 70 ST CMT. -> 5 ST GEL'S -> 2 ST HULLS
AND 70 ST CMT. MAX PRESSURE - 250 PSI CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED Signed: Marvin Shredt
STATE CORPORATION COMMISSION Well Plugging Supervisor

DATE _____
INV. NO. _____

JUL 31 1980
07-31-1980
CONSERVATION DIVISION
Wichita, Kansas