

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02030-00-00  
Spot: SESENE Sec/Twnshp/Rge: 8-10S-20W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: OESTERREICH Well Number: 1  
County: ROOKS Total Vertical Depth: 3824 feet

Operator License No.: 5285  
Operator Name: HANSEN, DANE G. - TRUST  
Address: PO BOX 187  
LOGAN, KS 67646

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.62 feet: 152 125 SX CMT  
Production: Size 5.5 feet: 3814 500 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

*11/22*

*124.28*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2000 2:00 PM  
Plug Co. License No.: 5285 Plug Co. Name: HANSEN, DANE G. - TRUST  
Proposal Rcvd. from: RICHARD L. WALLGREN, S Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered 12 yards of Redi-mix.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/22/2000 4:00 PM KCC Agent: CARL GOODROW

**Actual Plugging Report:**

8 5/8" set at 152' w/125 sxs cwc.  
5 1/2" set at 3814' w/500 sxs. two stage.  
Prod. Perfs 3558' - 3813'.  
Cut off 8 5/8" and 5 1/2" in bottom of cellar.  
Loaded 5 1/2" and 8 5/8" with 12 yards of Redi-Mix.

RECEIVED  
STATE CORPORATION COMMISSION  
11-30-00  
NOV 30 2000

Remarks: B&B REDI-MIX.

CONSERVATION DIVISION  
Wichita, Kansas

Plugged through: CSG

District: 04

Signed Carl Goodrow (TECHNICIAN)

*HD*

INVOICED  
DATE 12/1/00  
NOV 29 2000 Form CP-2/3  
200161041

NOV 27 2000

D. G. HANSEN

#1 OESTERREICH

8-10-20W  
SE SE NE

Contr. C-G DRILLING

ROOKS County

E 2251 RB

Comm.

Comp.

8-6-54

IP

3000 BOPD

DRAW DOWN

Tops	Depth	Datum
TOP	3297	-1046
HEEB	3480	-1229
TOR	3501	-1250
LANS	3519	-1268
B/KC	3736	-1485
CONG	3769	-1518
SIMP	3786	-1535
SH ARB	3807	-1556
ARB	3813	-1562
TD	3825	-1574

Casing

8" 152

5" 3814

DST 3599-3609/40", 2400' SW,  
BHP 1280#: DST 3814-24/1 HR,  
1665' OIL, 75' MDY OIL, BHP  
900#:

SWB 65 BO/1 HRS, ACID 500:

PALCO POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS