

2-17

API NUMBER 15-163-03315-0000

To: 6  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SE, SEC. 9, T 10 S, R 20 W/E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5058

Lease Name Hinkhouse Well # 2 SWD

Operator: Griggs Oil Inc.

County \_\_\_\_\_ Rooks 139.52

Name & Address 105 N. Market #800

Well Total Depth 4293 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Wilber Burg

Surface Casing: Size 8 5/8 feet 162

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_

Address 1707 East 10th Hays, Ks.

Company to plug at: Hour: AM Day: 17 Month: Feb Year: 19 89

Plugging proposal received from Wilber Burg

(company name) Griggs Oil Inc. (phone) \_\_\_\_\_

were: 8 5/8" 162' S.P. cwc w/125 sks cement; 5 1/2" casing set at 3918' w/200 sks cement.

D.V. tool at 1699' cwc w/600 sks cement. Squeeze also at 1696' w/85 sks cement. Open hole

375'. Washed over tubing got to 1460' SWD on vacuum. Recovered 1300' casing. Proposal

100 sks Class A Cement and 300 sks 60/40 Poz 8% Gel. Run tubing to 1300' Annulus open. Circulate with cement. Lay down and squeeze.

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour 3:00 PM Day: 17 Month: Feb Year: 19 89

ACTUAL PLUGGING REPORT Ordered 100 sks Class A Cement and 300 sks 60/40 Poz 8% Gel and

5 sks Hulls. Pumped in with pump truck. 1. Ran tubing to 1292'. Spotted 100 sks Class A cement and 300 sks 60/40 Poz 8% Gel with 5 sks Hulls mixed in.

2. Returned for an additional 250 sks 60/40 Poz 8% Gel.

3. Tubing at 660' Spotted 250 sks cement. No pressure. Cement plug dropped.

4. On Feb. 24, 1989 tubing at 754'. Plmped in 120 sks cement casing full. Witnessed by Gilbert Balthazor.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
Observe this plugging.

DATE: 3-7-89

INV. NO. 24072

Signed Marion J. Schmidt  
Marion J. Schmidt