

15-163-21858-0000

6

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW~~NE~~ SEC. 9, T. 10 S, R. 20~~W~~

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6171

Lease Name VEATCH Well # 1

Operator: HIGH PLAINS OIL EXP. INC.

County ROOKS 125.65

Name & Address P.O. Box 15162

Well Total Depth 3866 feet

LENEXA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

66215

Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B J TITAN ~~GREEN BIRD~~ <sup>KELSO CASING PULLING</sup> License Number 6050

Address OAKLEY KANSAS

Company to plug at: Hour: PM Day: 20 Month: 5 Year: 19 86

Plugging proposal received from TONY

(company name) KELSO CASING. (phone) \_\_\_\_\_

were: 8 5/8 @ 237 4/200sx. 5 1/2 @ 3865 4/100sx. PERE. 3786-3792.

ORDER SAND & COM. CNT. SHOOT & PULL PIPE. ORDER 250sx.

65/35 P02 10% GEL 2% DICEL (ECMOLITE) 5sx. HULLS BJTITAN

~~GREEN BIRD~~ <sup>KELSO</sup> CASING PULLING.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:PM Day: 20 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3786 SPOT 5sx. ON SAND W/BAILER

SHOOT & PULL PIPE, 55 HITS RECOVERED 1286' = F 5 1/2

TIEDN TO 8 5/8 MIX & Pump 3sx. HULLS 250sx. CNT. MIX. + 2sx. HULLS

MAX. PST 800' CLOSE IN 400' PLUG. COMP.

STATE CORPORATION COMMISSION  
6-16-86  
JUN 16 1986

18  
6-13-86

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 18 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 14139