

7-19 15-163-19434-0000

6 041203

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

SW SE NW, SEC. 9, T 10 S, R 20 WXB

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Veatch Well # A - 2

Operator: Okmar Oil Co.

County Rooks 123.17

Name & Address Box 723

Well Total Depth 3790 feet

Hays, Kansas 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 144 w/100

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B J. Services License Number _____

Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 19 Month: July Year: 19 90

Plugging proposal received from George Jorgenson

Okmar Oil'

(company name) _____ (phone) _____

were: 5 1/2 casing set at 3787 w/100 sks cement: perfs at 3565 - 3670.

Sq at 960; 1309; 1330; 1562; and 1810 w/500 sks cement.

.4 1/2" liner cemented from 1506 to surface.

8-17-90

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00PM Day: 19 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 4 1/2 casing w/15 sks cement w/1/4 lb f.c.

plus pumped in add 300 sks cement w/1/4 lb f.c. and 5 sks hulls mixed in cement.

Max 800 lbs. S.I. 400 lbs. Pumped in 8 5/8 casing w/35 sks cement w/1/4 lbs. f.c. mixed

in cement. Max 500 lbs.

Remarks:

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE: 8-23-90

INV. NO. 29038

J.L.S.

Signed Dennis L. Hamel
(TECHNICIAN)