

To: 6 070806
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-16 15-051 21141-00-00
API NUMBER 15- 4-21-76

S/2 SW NE, SEC. 34, T 12 S, R 18
3300 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Was National Oil Co.
Operator: American Warrior Inc.
Name & Address
Box 399
Garden City, Ks
Dean Ives

Lease Name Luecke Well # 1
County Ellis 119.89
Well Total Depth 3689 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 23 4

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Halliburton Cement Co. License Number
Address East Hwy 40 Hays, Ks. 67601

Company to plug at: Hour: AM Day: 16 Month: Nov Year: 19 89

Plugging proposal received from Dean Ives
(company name) American Warrior Inc. (phone)

were: 8 5/8" 234 ft. S.P. w/w 175 sks cement. 4 1/2" casing set at 3668' w/150 sks cement. 4 1/2" casing squeezed but no record. Perfs. 3404 to 3450' (Csg leaks). Proposal 250 sks 65/35 poz 8% gel and 5 sks hulls. Spot with tubing.

- 1. Run 2 3/8" tubing to 3480' Spot 100 sks cement w/3 sks hulls.
- 2. 2 3/8" tubing at 1510' w/60 sks cement w/2 sks hulls. Circulate cement and squeeze csg. Squeeze annulus. Shut in under pressure.

Plugging Proposal Received by *MJS* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 2:20PM Day: 16 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT American Warrior ordered 250 sks 65/35 poz 8% gel and 5 sks hulls. Spotted cement with tubing. 1. Run 2 3/8" tubing to 3480'. Spotted 100 sks cement w/3 sks hulls added in. 2. 2 3/8" tubing at 1510'. Spotted 60 sks cement w/2 sks hulls. Cement circulated at surface. 3. Squeezed 4 1/2" casing w/15 sks cement. Max pressure 1000 psig. Shut in at 950 psig. 4. Squeezed annulus. Did not take cement. Max pressure 400 psig. Shut in at 400 psig. Cemented by Halliburton Cement.

Remarks: 12-01-1989
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed *Marion J. Schmidt*
Marion J. Schmidt (TECHNICIAN)

DATE 12-7-89
INV. NO. 26659